ELECTRONYOS (EOS) SOLAR POWER SOLUTION PACKAGES

Tailored Installation Packages & Inventory Pairing Guide

The following turn-key solar power packages have been configured directly from inventory stock. Each package is matched based on electrical compatibility (system voltage, inverter MPPT thresholds), load profiles, mounting hardware, and protective switchgear.

Package 1: Basic / Small Home & Office (3.6 kW System)

Ideal for basic residential loads (fans, TV, fridge, lighting, laptops, and 1HP inverter AC).

Inverter	Growatt SPH 3600TL-BL-UP	Hybrid 3.6kW 2MPPT Single Phase	1	0,000	0,000
Battery	Growatt ABM 5.5-A1-H / HOPE5L-B1	5.12 kWh / 5.5 kWh Lithium-ion 48V	1	0,000	0,000
Solar Panels	Jinko 585N-72HL4-BD	585W Bifacial Half-Cut	6	0,000	0,000
Mounting	Antai PV Roof Mounting Set	Rail Kit for 8 Solar Panels	1	00	0
Protections	Suntree AC Guard / AC Breaker	AC Voltage Guard 63A + AC Breaker 32A	1 set	00	00
Distribution	Suntree SUNDB6WAY	6-Way DB Plastic Enclosure	1	00	00
				ESTIMATED TOTAL PACKAGE COST	**₦,0,200**

Package 2: Medium Home / Medium Office (6 kW System)

Ideal for standard households or medium offices (multiple refrigerators, freezers, 1.5HP – 2HP inverter ACs, office PCs).

Inverter	Growatt SIM 6000ES PLUS-H + BASE	Integrated 6kW Inverter System	1	0,000	0,000
Battery	Growatt ABM 5.5-A1-H	5.5 kWh 48V Lithium Battery	1	,000	,000

Solar Panels	Jinko 620N-66HL4-BD	620W Bifacial Half-Cut	10	,000	,000
Mounting	Antai PV Roof Mounting Set	Rail Kit for Solar Panels	2	0	00
Protections	Suntree AC/DC Protection Kit	AC Surge 20KA + DC Isolator 32A	1 set	00	00
Distribution	Suntree SUNDB12WAY	12-Way DB Enclosure Box	1	00	0
				ESTIMATED TOTAL PACKAGE COST	**₦000**

Package 3: Premium Executive Home / Corporate Office (8 kW – 10 kW System)

Designed for high-demand residential usage (multiple air conditioners, water pumps) or medium enterprise offices.

Inverter	Deye 8K-SG04LP3-EU	8kW 3-Phase Low Voltage Hybrid Inverter	1	0,000	00,000
Battery	Deye BATSE-F16-C	16 kWh Low Voltage Lithium Battery (48V)	1	000	000
Solar Panels	Jinko 720N-66HL5-BD	720W Bifacial Half-Cut	12	,000	000
Mounting	Antai Mounting Kit + Accessories	Rail sets + Mid/End Clamps	2	00	00
Accessories	Huawei ATS 63A	Auto Transfer Switch 63A 3-Phase	1	,000	,000
Protections	Suntree MCCB & AC Guard	MCCB AC 100A + DC Surge Protector	1 set	000	000
				ESTIMATED TOTAL PACKAGE COST	**₦000**

Package 4: Heavy Commercial / Industrial Setup (50 kW System)

Designed for factories, commercial complexes, large corporate headquarters, or mini-grids.

Inverter	Deye 50K-SG01HP3-E	50 kW 3-Phase High Voltage	1	00	00

		Hybrid Inverter			
Battery	Deye BOS-B-PACK16	HV Battery Pack 16 kWh B-PRO	3	0,000	0,000
Battery Control	Deye Control Box HV	BOS-B-PRO16KWH Control Box-ACC	1	,000	000
Battery Rack	Deye DEYERACK-3U-H	13-Layer Rack for HV Battery	1	00	,000
Solar Panels	Jinko 725N-66HL5-BD	725W Bifacial Half-Cut	70	,000	0,000
Mounting	Antai PV Mounting Sets	Rail Kits (8 panels each)	9	0	00
Protection/MCCB	Suntree MCCB AC 250A 4P	High Amperage Circuit Breaker	1	,000	00
				ESTIMATED TOTAL PACKAGE COST	**₦,000**

Key Installation Guidelines & Pairing Principles

- **Voltage Matching:** Low-voltage inverters (48V) like the Deye 8kW and Growatt 6kW are strictly paired with 48V/51.2V lithium modules. High-voltage inverters (50kW+) are paired with High-Voltage battery banks and matching control units.
- **Solar PV Sizing:** Panel string quantities are calculated to align with each inverter's maximum MPPT DC voltage range and current limits to optimize conversion efficiency and prevent over-voltage tripping.
- **Safety & Circuit Protection:** Every package incorporates matched Suntree protection components (DC/AC breakers, surge protection devices, and distribution boxes) sized specifically to peak operational amperage.